## $4'-6\frac{1}{2}"$ 4'-0" 4'-0" 4'-0" $1'-1\frac{1}{2}"$ 3'-10 3" 4'-0" 4'-0" **MIDWAY**

## PLATFORM LEVELING

LEVELING BLOCKS PLACED UNDER JOIST ENDS AT 4'-0" INTERVALS.

LEVELING BLOCKS TO BE ATTACHED THROUGH THE RUNNERS PRIOR TO SHEATHING

ALL THICKNESS OF PLYWOOD FLOORING IS 0'-3/4" THICK.

SHEATHING SEAMS WILL BE STAGGERED