


PLATFORM 3 LAYOUT

PLATFORM CONSTRUCTION
USING 2X6 NOMINAL BEAMS
FOR FRAME, JOIST, AND
RUNNER.

SHEATHED WITH 3/4" PLY.

SHEATHING GRAIN ORIENTED
PERPENDICULAR TO JOIST
DIRECTION


ALL SEAMS BACKED BY JOISTS
AND STAGGERED



PLATFORM 3 CONSTRUCTION

PLATFORM CONSTRUCTION
USING 2X6 NOMINAL BEAMS
FOR FRAME, JOIST, AND
RUNNER.

SHEATHED WITH 3/4" PLY.



PLATFORM 3A

PLATFORM CONSTRUCTION
USING 2X6 NOMINAL BEAMS
FOR FRAME, JOIST, AND
RUNNER.

SHEATHED WITH 3/4" PLY.

SHEATHING GRAIN ORIENTED
PERPENDICULAR TO JOIST
DIRECTION

ALL SEAMS BACKED BY JOISTS
AND STAGGERED

